

COLLAR DETAIL

C.M.P DIA.	NUMBER OF TIE BARS	NUMBER OF RING BARS
<u><</u> 30"	3	2
<u><</u> 36"	4	2
≤ 54"	6	3
> 54"	8	4

NOTES:

1. CONCRETE SHALL BE CLASS 3. CONCRETE CONTAINING FIVE SACKS OF CEMENT PER CUBIC YARD MEETS THE CRITERION FOR CLASS 3 CONCRETE.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS

CONCRETE COLLAR STORM DRAIN

DATE: MAY 2004	REVISED:		
APPROVED BY:	SCALE: NONE	DRAWING NO. 410	