

COLLAR DETAIL

DIA	NUMBER OF TIE BARS	NUMBER OF RING BARS	
≤ 30"	3	2	
≤ 36"	4	2	
≤ 54"	6	3	
> 54"	8	4	

NOTES:

CONCRETE SHALL BE CLASS 3. CONCRETE CONTAINING FIVE SACKS OF CEMENT PER CUBIC YARD MEETS THE CRITERION FOR CLASS 3 CONCRETE.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS

> CONCRETE COLLAR STORM DRAIN

DATE: MAY 2004	REVISED: JULY 2018	
approved by: JH	SCALE: NONE	drawing no. 410