

2. PULL BOX COVERS SHALL BE BOLTED AND INSCRIBED "STREET LIGHTING".

3. PULL BOXES PLACED OUTSIDE OF CONCRETE SIDEWALK AREAS, CONCRETE MEDIAN ISLAND AREAS, AND PLANTED STRIP AREAS LOCATED BEHIND CURBS OR A.C. DIKES SHALL BE 5(T) TRAFFIC PULL BOXES WITH STEEL COVERS AND SPECIAL CONCRETE FOOTING. SEE DRAWING NO. 602 AND CURRENT CALIFORNIA STATE STANDARD.

4. GROUT BOTTOM OF PULL BOX PRIOR TO CONDUCTORS BEING INSTALLED.

5. GROUTED BOTTOM SHALL BE SLOPED DOWN TO 1" DRAIN HOLE.

COUNTY OF SONOMA

DEPARTMENT OF TRANSPORTATION

AND PUBLIC WORKS

PULL BOX INSTALLATION NO. 5 PULL BOX

DATE: MAY 2004 REVISED: MAY 2018

APPROVED BY: SCALE: DRAWING NO. NONE 600