



NOTES:

1. CONSTRUCTION SHALL CONFORM TO THESE REQUIREMENTS EXCEPT AS OTHERWISE DIRECTED BY THE COUNTY ENGINEER.
2. IN AREAS WHERE CONCRETE SIDEWALKS WILL BE POURED AFTER THE POLE FOUNDATION IS INSTALLED, POUR FOUNDATION TO BOTTOM ELEVATION OF SIDEWALK. IN AREAS WITHOUT CONCRETE AROUND FOOTING, CONSTRUCT A 2'x2' CONCRETE PAD (4" THICK).
3. FOUNDATION BOLTS SHALL NOT BE CUT OFF FOR ANY REASON. EXTENSION COUPLERS SHALL NOT BE PERMITTED.
4. LEVELING OF BASE SHALL CONFORM TO THE REQUIREMENTS OF STANDARD DRAWING NO. 620.
5. ANCHOR BOLT DIMENSIONS PER MANUFACTURERS SPECIFICATION. ANCHOR BOLTS SHALL BE GALVANIZED STEEL.
6. CONCRETE SHALL BE CLASS 2 P.C.C. POURED AGAINST UNDISTURBED SOIL. SEE DRAWING NO. 618 FOR FOOTING DETAILS.

COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS

CONCRETE FOOTING DETAIL
STANDARD STREET LIGHT POLE

DATE: MAY 2004

REVISED: MAY 2018

APPROVED BY:

SCALE:
NONE

DRAWING NO.

JH

616