

**COPY OF BID ITEM LIST**  
(Not to be used for bidding Purposes)

**HEALDSBURG INTERMODAL FACILITY**  
**PHASE I**  
**FEDERAL PROJECT – CA-03-0577H**  
**COUNTY PROJECT – WO 7018**

<b>Bid Item</b>	<b>Reference</b>	<b>Bid Item Description</b>	<b>Quantity</b>	<b>Units</b>
1	10-1	Mobilization	1	LS
2	10-1.08	Water Pollution Control Plan (SWPPP)	1	LS
3	10-1.11	Traffic Control System	1	LS
4	10-1.12	Temporary Fence	2645	LF
5	10-1.13	Railroad Siding Track Removal Switch Removal and Reconstruction	1	LS
6	10-5	Clearing and Grubbing	1	LS
7	10-5	Tree Removal	15	EA
8	10-5	Protect Existing Trees	7	EA
9	10-3	Demolition and Pipe Removal, Abandonment and Restoration	1	LS
10	10-7	Earthwork Excavation	803	CY
11	10-7	Select Fill	631	CY
12	10-7	Trapezoidal Drainage Swale Bid Item 11	1100	LF
13	10-7	V-Drainage Swale Bid Item 12	150	LF
14	10-9	Remove and Salvage Water Meter	3	EA
15	10-9	Domestic 1-1/2" Water Service	1	EA
16	10-9	Domestic 2" Water Service	1	EA
17	10-9	Depot 2" Dual Meter Water Service	1	EA
18	10-9	8-inch PVC Water Main w/connections	380	LF
19	10-9	Fire Service Stub w Cap	1	LS
20	10-9	Sanitary Sewer Line W/Connections	335	LF
21	10-10	Temporary/Permanent Erosion Control	1	LS
22	10-11	Aggregate Base (Class 2)	830	CY
23	10-11	Drain Rock	87	CY
24	10-11	Rock Slope Protection	10.5	CY
25	10-12	Hot Mix Asphalt	1071	TON
26	10-13	Concrete Curb and Gutter	1093	LF
27	10-13	Concrete Curb	988	LF
28	10-13	Concrete Sidewalk City Standard	434	SF
29	10-13	Concrete Sidewalk Thickened Edge	5673	SF
30	10-13	On Site Concrete Valley Gutter	68	SF
31	10-13	On Street Concrete Valley Gutter	500	SF
32	10-13	PCC Bus Pad	450	SF
33	10-13	Concrete Driveways	700	SF
34	10-13	Concrete Curb Ramps	7	EA
35	10-13	Wheel Stops	3	EA
36	10-13	Dry Stack Retaining Wall	880	SF
37	10-14	Furnish and Install Drainage - 15" A2000	55	LF
38	10-14	Furnish and Install Drainage - 18" A2000	767	LF
39	10-14	Furnish and Install Drainage - 12" CI III	25	LF
40	10-14	Furnish and Install Drainage - 15" CI III	38	LF

41	10-14	Furnish and Install Drainage - 18" CI IV	50	LF
42	10-14	Furnish and Install Drainage - 6" DIPW 4lf 8" CMP	220	LF
43	10-14	Furnish and Install Drainage - 10" DIP	54	LF
44	10-14	Furnish and Install Drainage - 12" HDPE	363	LF
45	10-14	Furnish and Install Drainage - 6" HDPE	88	LF
46	10-14	Cathodic Protection	11	EA
47	10-15	Furnish and Install Type G1 Inlet	5	EA
48	10-15	Furnish and Install COH Curb Inlet	7	EA
49	10-15	Construct Field Inlet Detail System	1	LS
50	10-15	Construct Flared End Section with Special Grate	1	EA
51	10-15	Construct New Storm Drain Manhole over existing pipe	1	EA
52	10-15	Construct Roof Drain Leader Connection	3	EA
53	10-15	Connect new 18" Pipe into existing manhole	1	EA
54	10-16	Fire Hydrant	1	EA
55	10-18	Chain Link Fence - 4' Feet Height	430	LF
56	10-18	Chain Link Fence - 5' Feet Height	1205	LF
57	10-18	Man Gates	2	EA
58	11	Lighting and Electrical Systems	1	LS
59	11-1.24	Remove Pavement Striping, Markers and Markings	1	LS
60	11-1.24	Furnish and Install Raised Pavement Markers	1	LS
61	11-1.25	Flashing Crosswalk Signage with Ped Push button	1	LS
62	11-1.26	Thermoplastic Traffic Stripe and Markings	1	LS
63	11-1.27	Paint Traffic Stripe	1	LS
64	11-1.28	Parking Lot and Roadway Signs	21	EA
65	12	Irrigation	1	LS
66	13	Landscaping	1	LS
67	14	Galvanized Steel Railing	1	LS
68	14	Bollards	1	LS
69	15	Site Furnishings	1	LS