



NOTES:

1. SIX (6) BUMPER BLOCKS SHALL BE REQUIRED FOR EACH SIGN INSTALLATION.
2. BUMPER BLOCKS SHALL BE PLACED AS DIRECTED BY THE ENGINEER. WITH RAPID SET EPOXY PER MANUFACTURER'S SPECIFICATION.
3. SEE DRAWING NO. 712A FOR FOUNDATION DETAILS.

**COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS**

**BARRICADE PLACEMENT
FOR R1 SIGN INSTALLATION
IN PAINTED ISLAND**

DATE: MAY 2004

SCALE:
NONE

DRAWING NO.

REV. DEC. 2014

708