



NOTES:

1. CYLINDER MATERIAL SHALL BE THINWALL ABS OR PVC PLASTIC PIPE.
2. EXISTING MONUMENT CORE, CONCRETE COLLAR AND OTHER MATERIAL SHALL BE REMOVED TO A DEPTH OF 2-1/2" BELOW TOP OF EXISTING MONUMENT.
3. DO NOT DISTURB EXISTING MONUMENT CORE. IF DISTURBED, CONTRACTOR SHALL REPLACE AS PER DRAWING NO. 218 AT HIS EXPENSE FOR INSTALLATION AND SURVEY TIME NECESSARY TO RELOCATE THE ORIGINAL POSITION.

COUNTY OF SONOMA
DEPARTMENT OF TRANSPORTATION
AND PUBLIC WORKS

SURVEY MONUMENT
COVER REPLACEMENT

DATE: JULY 2018

REVISED:

APPROVED BY:

SCALE:
NONE

DRAWING NO.
218A